



APPRENTICE PRACTICAL PROJECT 2025 INSTRUCTIONS

Please read these carefully and adhere to these instructions.

PROJECT INSTRUCTIONS

- All corners mitered other than boxed corners
- H&S is most important at all times. If not adhered to, you will be disqualified.
- Build to BEST trade practice.
- Check material sizes as may vary from plan dimensions.
- Screw fixed only
- Build to the drawings and written instructions supplied
- All screws to be countersunk below the surface
- There are NO spare pieces, check twice cut once
- Accuracy is important.
- Each support cleat fixed using 3x40mm screws, centered on cleat, screws 50mm in from end of cleats.
- Use 90mm screws on TGV mitered corners
- Box corners to be flush/square.
- Fit the base snug for length and even for width.
- Drainage is created with x1 25mm hole in center of each base boards.
- Top cap overhang TGV rails by 25mm
- Top rail screw positioned 20mm from mitered corners and centered on TGV and box corner members